


## ACCESSIBLE PARKING REQUIREMENTS

TOTAL PARKING SPACES PROVIDED	MINIMUM NUMBER OF ACCESSIBLE SPACES OF ACCESSIBLE SPACES REQUIRED	MINIMUM NUMBER OF ACCESSIBLE SPACES REQUIRED TO BE VAN ACCESSIBLE
1 TO 25	1	1
26 TO 50	2	1
51 TO 75	3	1
76 TO 100	4	1
101 TO 150	5	1
151 TO 200	6	1
201 TO 300	7	2
301 TO 400	8	2
401 TO 500	9	2
501 TO 1000	2% OF TOTAL	1 IN EVERY 6 ACCESSIBLE SPACES
1001 AND OVER	20 PLUS 1 FOR EACH 100 OVER 1000	1 IN EVERY 6 ACCESSIBLE SPACES

SECTION 4.1.2 (5) OF THE AMERICANS WITH DISABILITIES ACT (ADA).  
SEE 4.1,2,(5) (d) FOR MEDICAL CARE FACILITIES

**NOTES:**

1. ALL 12"x18" ACCESSIBLE SIGNS SHALL BE MOUNTED AT SEVEN FEET FROM GRADE TO BOTTOM EDGE OF SIGN FACE (MUTCD). MOUNTING HEIGHT CAN BE REDUCED TO FIVE FEET IF PLACED IN AN AREA BETWEEN SIDEWALK AND BUILDING FACE IN WHICH PEDESTRIANS ARE NOT EXPECTED TO USE.
2. REFER TO MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (MUTCD) U.S. DEPARTMENT OF TRANSPORTATION AND NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SUPPLEMENT.
3. IF ACCESSIBLE ROUTE IS A RAISED SIDEWALK AREA, THEN RAMPS ARE REQUIRED AT LOADING ZONE AREA.



ONE OUT OF EVERY SIX (6) ACCESSIBLE SPACES, BUT NOT LESS THAN ONE, IS REQUIRED TO BE VAN ACCESSIBLE.

### PARKING SPACE PAVEMENT MARKINGS

Ⓐ

R7-8A  
12"x6"

MUTCD  
R7-8  
12"x18"

12"x9"

Ⓑ

12"x18"

ACCESSIBLE RESERVED  
PARKING SIGN  
(OPTIONAL)

Ⓒ

MUTCD  
R7-8  
12"x18"

12"x9"

SEE STANDARD NO. 714.1 FOR  
SUPPLEMENTAL SIGN DETAIL

SEE STANDARD NO. 713.1 & 714.1 FOR SUPPLEMENTAL SIGN DETAIL

NOT TO SCALE